

# WINDOWS



## Building a High-Performance Window Wall Large triple-glazed windows create an energy-efficient alternative to traditional storefront glazing

BY NATE HAYWARD

In June 2019, after years of leasing commercial office space, we broke ground on a new office building for my company, Hayward Design Build, in South Hero, Vt. Our firm is known for building high-performance custom homes and light-commercial buildings in northern Vermont, and we approached the construction of our new headquarters in the same manner.

Some of the building's high-performance features include a super-insulated double-wall shell with a carefully taped-off Intello Plus vapor control barrier membrane; triple-glazed windows set in rugged fiberglass frames (some with insulated glass units (IGUs)

as large as 7 feet high by 6 feet wide); a VRV (variable refrigerant volume) mini-split system, which supplies heating and cooling to offices and common areas with localized thermostats that allow occupants to control the temperature of individual spaces; and two large-capacity ERV (energy recovery ventilator) units to provide a balanced air supply throughout the building.

**Architectural features.** The building was designed to accommodate multiple tenants on three floors. On the second- and third-floor mezzanine levels, we planned for shared office space split between my design-build company, a local law firm, and a real estate company,

## Balloon-Framed Entry Walls

**"Hot" roof assembly.** Parallel-chord scissor trusses, Zip System roof sheathing, high-temp peel-and-stick membrane and standing-seam metal roofing. At interior, Insulweb netting, dense-pack cellulose, vapor control membrane applied to underside of trusses, and  $5/8"$  Type X drywall installed over  $1\text{--}1/8"$  metal furring.

Crib wall ties back to main roof framing

7/16" Zip sheathing  
at top plate

1/2" Zip sheathing  
gusset plates, 4' o.c.  
(at sheathing blocking)

Built-up 2x headers framed between LSL studs


Double 2x6 —  
blocking installed  
at horizontal  
sheathing seams

Sheathed portions of entry bump-out walls provide lateral stability

- 17'-high entry walls  
balloon-framed with  
LSL studs (yellow)

18'-0"-long footbridge connects second-floor exterior entry to parking area

**Jamb Detail  
(Plan View)**



**Window units:** Triple-glazed "outie" fiberglass fixed windows, nail flanges set in continuous bead of sealant, flashed with vapor-open Siga Fentrim tape

**12"-wide double studwall assembly:**  
2x6 exterior bearing wall with 2x4 interior nonbearing studwall, 1/2" Zip System wall sheathing (acts as air barrier). At interior, Insulweb netting, dense-pack cellulose, vapor control membrane (seams sealed with Siga Rissan tape), and 5/8" Tyne X drwall.

LSL members were used to balloon-frame the bump-out entry's 17-foot-high wall, while 2-by stock was used to infill shorter-length pieces such as trimmer studs, sills, and blocking. Sheathed areas on the south, east, and west walls helped provide lateral stability to these tall walls with big openings (the sheathing was nailed off per an engineer's specifications).

while the first floor was divided into two units, one occupied by a local catering company. We provided at-grade access to the first and second floors, which eliminated the expense of installing an elevator to meet ADA requirements (the third-floor mezzanine has less than 1,000 finished square feet and doesn't require ADA access).

**Structural.** The wall system throughout the entire building is a 12-inch-thick double-stud wall with a 2x6 exterior bearing wall and 2x4 nonbearing interior wall—the thick wall is essentially an insulation holder for dense-pack cellulose. A structural engineer helped design a steel frame, which was needed to support the wood I-joist floor system on multiple floors and the quadruple-ply ridge beam truss running the length of the building. The “hot” roof was framed with parallel-cord trusses, dense-packed, and the roof sheathing

was covered with a high-temperature self-adhered roofing underlayment, then metal roofing.

**Tall walls with big openings.** The south-facing bump-out entry was a transverse gable-end wall. We used engineered LSL studs to balloon-frame the entry's 17-foot-high double-stud walls, installing them one stick at a time rather than building the wall and standing it up, then infilled with 2x6 and 2x4 stock as needed for shorter-length pieces like jack studs, sills, and blocking (see illustration, above).

We sheathed the walls with 1/2-inch Zip System sheathing. We provided double 2x6 horizontal blocking between LSL exterior-side studs at horizontal seams and nailed off the sheathing in a tight pattern per the structural engineer's specifications (the small sheathed areas on the bump-out's south, east, and west walls helped provide


## Selecting a High-Performance Window Package

**A common challenge** with office buildings and HVAC is satisfying the comfort level of all the occupants. Battles for control over too few, centrally located thermostats can be commonplace. Combine this with occupants cracking open windows to cool off, warm up, or let in fresh air, and you have the recipe for an unbalanced, inefficient HVAC system.

In an effort to mitigate these issues, we installed a VRV mini-split system with localized thermostats allowing occupants to control the temperature of their individual offices and small common areas. For fresh air, we installed two large-capacity Zehnder ComfoAir Q600 ERV units to provide a balanced air supply throughout the building. The planned ERV units afforded us the opportunity to install mostly fixed windows throughout the building, the simple design of which provided substantial savings in window costs and later, energy. After a year of occupancy, the combination of the VRVs, ERVs, and fixed high-performance windows has proved to be a success. Although on occasion, occupants have cracked open some of the few code-mandated operable egress windows, which necessitated a polite request to close them and rely on the HVAC system.

**Window options.** All-fiberglass window frames are durable, and I like that they are silica-based products that will expand and contract a bit with the glazing. So I selected Fibertec Windows ([fibertec.com](http://fibertec.com)) out of Canada. Its 300-Series windows offer triple-pane glazed windows in sturdy 3 1/4-inch-deep fiberglass frames, and they're available in large sizes (the 7'-0" x 6'-0" windows we used for the entry were the maximum size they make). The windows' IGUs are one piece of glass with simulated divided light (SDL); the SDL effect is created with 1 7/8-inch-wide surface-applied muntins.

The U-Factor numbers of the Fibertec windows are pretty phenomenal at 0.14 to 0.17 (0.32 or less is considered a good U-factor in a cold climate). The company was amenable to our using different specialty coatings for the windows on different sides of our building, which is not always the case with window manufacturers. Our window glazing package included a higher SHGC (solar heat gain coefficient) of 0.46 for south-facing windows, while on east-, west- or north-facing windows, we selected a lower SHGC of 0.27. The visible transmittance (VT) numbers increased with the rise in solar heat gain coefficient (see photos, below) —*N.P.*



East-, west- and north-facing windows had an SHGC of 0.27 (above left), while south-facing windows had a higher SHGC of 0.46 (above right). Crew members move a 7-foot-high-by-6-foot wide, 500-pound fixed window to the lift staging area on a footbridge that connects the entry to the parking area; they pass under a wall-mounted mini-split unit in the entry's reception area (right).

## BUILDING A HIGH-PERFORMANCE WINDOW WALL

Prior to installing the big windows, the crew cuts Zip System Stretch Tape flashing to length inside (1) and installs it on the sill (2). Four crew members manhandle the 500-pound window onto the lift, transferring the unit from a carpeted mover's dolly using 8-inch-diameter hand-held vacuum cups to grip the unwieldy window (3). The JLG rental lift is equipped with a "skylazer" tray to support the base of the window. The unit is attached to the personnel cage with ratchet straps, with pieces of XPS insulation used as padding. Prior to installation of the window, a continuous bead of Geocel Pro-Flex tripolymer sealant is applied around the opening where the window nailing flange will be set (4).



The window is set on 1/2-inch bearing blocks, then leveled from the interior (5). The nailing flanges are nailed off with stainless steel roofing nails (6). Before the crew installs the vapor-open sill flashing tape, a dab of sealant is applied to each corner to seal the opening where the window frame and nailing flanges intersect (7). After the sill flashing tape is installed, tape is applied over the open corners (see photo 11, facing page). Then the jamb flashing tape is applied (8). The top inch of the tape is peeled back and the tape worked down the window to adhere it a few inches at a time. The jamb tape is lapped onto the sill flashing tape.



After the jamb flashing strips are installed, pieces of Siga tape are applied at the “open corners” at the top of the window unit on both sides (9). The head flashing strip is then applied, lapping onto the jamb flashing (10). On a lower window, a small piece of flashing tape is added to seal the intersection of the three planes (11). The four large south-facing window units are installed working counterclockwise from the top right. Here, the last of the 7'-0" x 6'-0" entry windows is installed (12). Four smaller, 420-pound fixed windows on the east and west walls (two per wall), as well as a window unit high in the gable-end wall, were installed on the previous days. The finish entry is clad with Galvalume siding over a drainable housewrap (13).

lateral stability to these tall walls with their big openings). Finishing up the wall framing, we joined the two stud walls together with plywood gusset plates at 4-foot centers and installed crib walls to tie back to main building’s roof framing. After we installed and taped off the remaining Zip System sheathing, we set the entry’s parallel-cord scissor roof trusses, which ran back to the main ridge.

**Muscling windows into place.** It took four crew members using 8-inch hand-held vacuum cups (wpg.com) to lift the 500-pound window onto a carpeted mover’s dolly. The unwieldy unit was then rolled out onto the footbridge, which was used as a staging area to lift the windows into place. The JLG 600S rental lift came equipped with a “skylazer” tray attached to supporting forks under the lift’s person-

nel basket. Again, using the vacuum cups, we lifted the window into the tray, padded it out with pieces of XPS insulation, then attached the unit with ratchet straps and lifted it up to the rough opening. The unit was placed on setting blocks on either end of the opening and leveled as needed. The windows were then sealed and flashed (see photos 1 to 12 for the flashing sequence).

**Finishing up.** We installed Hydrogap drainable housewrap over the Zip System sheathing to provide a small drainage plane and installed Galvalume siding on the entry bump-out’s three walls.

*Nate Hayward is the owner and principal of Hayward Design Build, in South Hero, Vt.*